

**AMENDMENT NUMBER 1**  
Amendment Date: **March 7 2019**

**RJRD 2019-01 Lower Lake Dam Rehabilitation**

A. This Amendment shall be considered part of the bid documents for the above-mentioned project as though it had been issued at the same time and shall be incorporated integrally therewith, whether physically attached or else by reference. Where provisions of the following supplementary data differ from those of the original bid documents, this Amendment shall govern and take precedence.

B. Bidders are hereby notified that they shall make any necessary adjustments in their estimates as a result of this Amendment. It will be construed that each bidder's proposal is submitted with full knowledge of all modifications and supplemental data specified herein.

**C. 1. Modifications and Clarifications:**

Except as described below, the original bid document remains unchanged. The bid documents are modified and/or clarified, as follows:

1. **Section 00410 – Bid Form:** On Table 2 – Unit Price Bid of Article 4.01, Item No. 5. “Coarse Aggregate No. 8” ***should read*** Item No 5. “Coarse Aggregate No 57”.
2. **Section 00410 – Bid Form:** On Table 2 – Unit Price Bid of Article 4.01, Assumed Quantity of Item No. 11 – Type 3 Concrete – C.I.P. Reinforced Concrete Walls ***should read*** “41” Cubic Yards.
3. **Section 02374 - GEOWEB® Cellular Confinement System:** In Article 2.06.A and 3.02.F.1 the reference to coarse aggregate “No. 8” ***should read*** “No. 57”.
4. **Section 00410 - Bid Form, Article 3.01A:** Bidder must also sign the amendment and submit it with their bids.

**C.2. Answers to Questions:**

Below are answers to the comments/questions that were discussed during the Pre-Bid meeting last week and/or were received by telephone before the deadline.

1. Q. Confirm Estimate
  - a. **Engineer’s Opinion of Probable Construction Cost = \$574,000**
2. Q. Permitting Documents to be made available prior to construction?
  - a. **USACE PCN will be provided prior to initiation of construction**

- 3. Q. Alternatives to metal steps?
  - a. **Contractors may propose alternatives to the metal staircase. However, the PVC outlet pipe from the valve box and the existing bearing plate along the building must remain accessible.**
  
- 4. Q. Confirm cut-fill.
  - a. **Based on the Opinion of Probable Construction Cost there will be a net cut of approximately 570 CY.**
  
- 5. Q. Confirm owner/engineer is responsible for hiring independent lab and completing compaction testing.
  - a. **All lab testing, including proctor testing in advance of fill placement, shall be completed at an independent lab selected by the Owner.**
  - b. **Pursuant to Specification 02323, Section 3.03.I. Owner/Engineer shall perform compaction testing on soils prior to use as fill and, upon placement and compaction, the Engineer will determine the in-place moisture and field dry density.**
  
- 6. Q. Tree clearing restrictions due to endangered species?
  - a. **Per the U.S. Fish and Wildlife Service – Ohio Ecological Services Field Office letter dated July 10, 2018 (included in Appendix D of the USACE 404, Pre-Construction Notification) “There are no critical habitats within your project area under this office’s jurisdiction.”**

**C.3. Instructions:**

Bidder must acknowledge this Amendment by signing below, by acknowledging receipt of Addendum 1 in SECTION 00410, the Bid Form, Article 3.01A, and by attaching the signed Amendment to the Bid Form:

Company Name \_\_\_\_\_

Contact Person \_\_\_\_\_

Signature \_\_\_\_\_

Date \_\_\_\_\_

Addendum issued MARCH 7, 2019